



Compliance Statement

Unscreened Class E / Category 6 ISO/IEC, EN & ANSI/TIA Three Connector Permanent Link

Reichle & De-Massari AG
Binzstrasse 32,
CH-8620 Wetzikon, Switzerland

Compliance Statement No. 0473-3P-1211287

This type of Class E / Category 6 Unscreened Three Connector Permanent Link has been tested by 3P Third Party Testing. The testing has shown compliance with the Class E electrical performance requirements of edition 1.0 of ISO/IEC 11801-1:2017, edition 1.0 of ISO/IEC 11801-2:2017, CENELEC EN 50173-1:2018 and the Category 6 electrical performance requirements of ANSI/TIA-568.2-D:2018. The Compliance Statement is valid for the actually tested permanent link samples, consisting of the listed components. The Compliance Statement is valid until 7 June 2024.

| | | |
|-----------------------------|--------------------------------------|---|
| Cables: | <i>Horizontal Cable (15 – 75 m),</i> | <i>Unscreened Cat. 6 (P/N: see annex 1)</i> |
| | <i>Qualification Status:</i> | <i>Manufacturer verified</i> |
| Conn. Hardware: | <i>Modular Jack,</i> | <i>Unscreened Connection Module Cat. 6 (P/N: see annex 1)</i> |
| | <i>Qualification Status:</i> | <i>Manufacturer verified</i> |
| Consolidation Cords: | <i>(10 m),</i> | <i>Unscreened Cat. 6 CP cord (P/N: see annex 1)</i> |
| | <i>Qualification Status:</i> | <i>Manufacturer verified</i> |

Hoersholm, 7 December 2021


Peter Freiberg Kaas
Test Responsible

3P Third Party Testing ApS
Agern Alle 3
2970 Hørsholm
Denmark

www.3Ptest.dk

Hoersholm, 7 December 2021


Jens Rytter Petersen
General Manager




Annex 1

Compliance Statement No. 0473-3P-1211287

| Part number | Description |
|-------------|--|
| R35057 | Installation Cable Cat. 6, U/UTP, 4P, 450 MHz, LSZH, grey, Eca, 500 m |
| R35056 | Installation Cable Cat. 6, U/UTP, 4P, 450 MHz, PVC, grey, Eca, 500 m |
| R809796 | Installation Cable Cat. 6, U/UTP, 4P, 250 MHz, LSZH, grey, 305 m |
| R809797 | Installation Cable Cat. 6, U/UTP, 4P, 250 MHz, PVC, grey, 305 m |
| R814603 | Installation Cable Cat. 6, U/UTP, 4P, 250 MHz, LSZH, grey, 500 m |
| R820801 | Installation Cable Cat. 6, U/UTP, 4P, 250 MHz, LSZH, grey, 905 m |
| R842467 | Installation Cable Cat. 6, U/UTP, 4P, 250 MHz, LSZH, grey, Cca, 500 m |
| R813808 | Installation Cable Cat. 6, U/UTP, 4P, 250 MHz, LSZH, grey, 500 m |
| R814603 | Installation Cable Cat. 6, U/UTP, 4P, 250 MHz, LSZH, grey, 1000 m |
| R852286 | Installation Cable Cat. 6, U/UTP, 4P, 250 MHz, LSZH, grey, B2ca,305m, ETR |
| R854455 | Installation Cable Cat. 6, U/UTP, 4P, 250 MHz, LSZH, grey, B2ca, 500m, ETR |
| R845613 | Installation Cable Cat. 6, U/UTP, 4P, 250 MHz, LSZH, grey,305 m |
| R815141 | Installation Cable Cat. 6, U/UTP, 4P, 350 MHz, LSZH, grey, 500 m |
| R305283 | Installation Cable Cat. 6, U/UTP, 4P, 450 MHz, LSZH, grey, Eca, 1000 m |
| R317603 | Installation Cable Cat. 6, U/UTP, 4P, 450 MHz, PVC, grey, 305 m |
| R802920 | Installation Cable Cat. 6, U/UTP, 4P, 450 MHz, LSZH, grey, Eca, 305 m |
| R845864 | Installation Cable Cat. 6, U/UTP, 4P, 450 MHz, LSZH, grey, B2ca, 500 m |
| R861314 | Installation Cable Cat. 6, U/UTP, 4P, 450 MHz, LSFRZH, grey, Dca, 500 m |
| R821301 | Installation Cable Cat. 6, U/UTP, 4P, 450 MHz, LSFRZH, grey, Dca, 1000 m |
| | |
| R302373 | Connection Module, Cat.6,1xRJ45/u |
| R304328 | Connection Module, Cat.6,1x100xRJ45/u |
| R304374 | Connection Module, Cat.6,1xRJ45/u, Snap in |
| R305114 | Connection Module, Cat.6,1xRJ45/u,spec. |
| R308734 | Connect. Module, C6,1x100xRJ45/u, Snap-In |
| R512369 | Module RJ45/u-C6-sn-bk-24 |
| R810597 | Connection Module-Cat.6 Eco-1xRJ45/u |
| R810598 | Connection Module-Cat.6 Eco Snap-1xRJ45u |
| R813810 | Module RJ45/u C6-ks1 |
| R814553 | Connection Module-C6-100xRJ45/u-sp |
| R823889 | Connection Module-Cat.6 Eco-1xRj45/ks |
| R823890 | Connection Module-Cat.6 Eco-24xRj45/ks |
| R875558 | Connection Module, Cat.6/u, fr, Polycab |
| R875559 | Connection Module, Cat.6/u, sn, Polycab |
| | |
| R307090 | CP Cable Cat.6, U/UTP, 4P, LSZH, RJ45/u-RJ45/u, 10m |

Hoersholm, 7 December 2021


Peter Freiberg Kaas
Test Responsible

3P Third Party Testing ApS
Agern Alle 3
2970 Hørsholm
Denmark

www.3Ptest.dk

Hoersholm, 7 December 2021


Jens Rytter Petersen
General Manager